# Final X-ray Assessment Results and Explosive Destruction Technologies (EDT) Path Forward



**December 13, 2011** 

Presented to:

Kentucky Chemical Demilitarization Citizens' Advisory Commission/Chemical Destruction Community Advisory Board

Presented by:

**Jeff Brubaker** 

Site Project Manager
Blue Grass Chemical Agent-Destruction Pilot Plant















## X-ray Assessment Final Findings

#### A Partnership for Safe Chemical Weapons Destruction

- All 96 H-filled munitions in sample contained heel
  - Average heel 54.8 percent
  - Minimum heel 15 percent
  - Some weapons were completely solidified
- Additional heel along side
- 36 overpacked munitions had liquid in the fuze well
  - Two showed liquid inside overpack
- Estimated average heel for entire stockpile estimated to be between 50.6 and 59 percent
- Approximately 6,100 munitions estimated to have greater than 59 percent heel




Clearly visible heel

No liquid line visible



### **Three Options Available**

#### A Partnership for Safe Chemical Weapons Destruction



Images taken May 25, 2011, courtesy Blue Grass Chemical Activity.

# 1) Process problematic projectiles with current BGCAPP design/facility

- Pros: No changes to existing equipment, no additional equipment expenditure, no permit modification required
- Cons: Manual intervention required, worker safety risk increased, strain on equipment, extends H destruction schedule

#### 2) Make design modifications to BGCAPP facility

- Pros: No new permit required
- Cons: Difficult to incorporate changes after construction, some manual intervention still likely, potential increase to worker safety risk, effect on schedule unknown (facility modification and H destruction)

#### 3) Use an EDT to process mustard projectiles

- Pros: Worker safety improved, provides H destruction schedule stability
- Cons: New permit required, additional facility required



# Site Project Manager's Insights for Path Forward

- Several factors are important to destruction process selection
  - Worker safety
  - Environmental compliance
  - Process efficiency
  - Cost and schedule
- Current design has limitations or unknown capability
  - Ability to remove stuck bursters without manual processing
  - Ability to wash out solidified agent
  - Maintenance concern with transfer of solids past drain step
  - Not able to process large heels in Metal Parts Treater
- ACWA will work with citizens' groups to receive stakeholder input on considerations for final decision
- No final decisions will be made until the National Environmental Policy Act process is complete



### **Viability of Path Forward**

- Project leaders expected X-ray Assessment to show a large number of problematic munitions
- In May 2011 ACWA requested that Bechtel Parsons Blue Grass begin an Explosive Detonation Technology (EDT) Feasibility Study
  - Analysis considered 2009 National Research Council EDT report, other completed EDT studies and recent information from Chemical Materials Agency
  - Researched several questions
    - Can EDT fit into current plant design?
    - Would EDT affect worker safety?
    - Where would an EDT facility be built?
  - Neither non-contaminated rocket motors nor nerve agent munitions were included in the study



# **Explosive Destruction Technology Feasibility Study**

A Partnership for Safe Chemical Weapons Destruction

#### **Considerations**

National Research Council 2009 EDT Assessment


Updated Operational Experience Within CMA

Regulatory Requirements

Blue Grass Army Depot

Blue Grass Chemical Activity

# BGCAPP Operational Philosophy



- Protect the workforce, public and environment
- Minimize or eliminate human interface with weapons
- Minimize or eliminate additional waste streams

# Feasibility Study Deliverables

- 1) Recommend best-value technology
- Same technologies offered by National Research Council
- 2) Recommend location on BGCAPP footprint
  - Located safe distance from personnel buildings, BGCAPP plant, munitions storage igloos
- 3) Develop conceptual life-cycle cost/schedule



### **Feasibility Study Recommendations**

- It is feasible to integrate an Explosive Destruction Technology system for disposal of mustard projectiles at Blue Grass
  - A smaller facility utilizing planned support resources
- All three commercial systems likely could process 15,000+ mustard projectiles
- Blue Grass site location to address several issues
  - Maintain safe distance from personnel buildings and munitions storage areas
  - Adapt to existing utilities
  - Must have endorsement of Blue Grass Army Depot and Blue Grass Chemical Activity



# Site Project Manager's Recommendation

- We are looking to citizens' groups and EDT Working Group for input to these options or additional potential options
  - Request recommendation by January 2012
- It is important to me that the community is behind any decision that affects the program
  - ACWA will remain transparent throughout the decision-making process
  - We will continue to work closely with citizens' groups and the EDT Working Group



Example of stockpile projectile with overpack container.



#### A Partnership for Safe Chemical Weapons Destruction

# **Questions?**

For more information about the Blue Grass Chemical Agent-Destruction Pilot Plant project, please contact the Blue Grass Chemical Stockpile Outreach Office at (859) 626-8944